

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

139679

For corners in

Oakland
(County)

Located In:
Highland Township

Corner Code #

LIBER 19872 PAGE 91
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
04/22/1999 07:54:23 A.M. RECEIPT# 22152
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

	T3N	R7E	D-1
	T	R	
	T	R	
	T	R	
S	T	R	SURVEY & REMONUMENTATION
S	T	R	
S	T	R	
S	T	R	MAR 21 2000

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 4-15-99 JS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____ SECTION _____

5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Huston K. Kennedy, in a field survey on March 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1815- 1826GLO Holmes, D.S.; No post was set, no witnesses
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner was not set during the original government survey but has been perpetuated in two positions. A capped 1/2" Iron Rod #17022 and a large rock w/chiseled "+" the distance between the found capped 1/2" Iron Rod and the large rock with chiseled "+" is S15°E 1.22 feet. I accepted the large rock w/chiseled "+" as the best evidence of the corner. The corner as found is 1.19 feet North of the township line. The South 1/4 corner of Section 32, T4N, R7E, Rose Township (D-13) is located 324.21 feet to the East. The corner was reset on the township line and is located in a old fence, tree and rock row extending to the East & West. I found no evidence to dispute the location of the found large rock w/chiseled "+".

FIELD MEASUREMENTS BETWEEN

D-1 to C-1

No GLO
No sidwell or plat distances
2709.09 Ft. (GPS-MEA)

D-1 to E-1

No GLO
No sidwell or plat distances
2715.83 Ft. (GPS-MEA)

D-1 to D-13

No GLO
324.21 Ft. (GPS-MEA)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-1 I replaced the large rock w/chiseled d "+" with a 4" diameter Concrete Monument with 1/2" Iron Rod 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 on the town line
Due West 18.30' Set Mag Nail & Remon Washer South face 26" Oak
N08°E 27.70' Set Mag Nail & Remon Washer West face 17" Cherry
S24°E 18.35' Set Mag Nail & Remon Washer NE face 13" Maple
S30°W 34.25' Set Mag Nail & Remon Washer SE face 20" Oak
East 324.21', South 1/4 corner Section 32, T4N, R7E, Rose Township (D-13)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 4-15-99

