

SURVEY & REMONUMENTATION

MAY 24 2000

SECTION

LIBER 20329 PG 644

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
(County)

Located In:
Highland Township

Corner Code #

1. Public Land Survey

T3N R7E D-3

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. _____ Recorded Plat

5. Private Claims _____

273078

LIBER 20329 PAGE 644
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
07/29/1999 11:46:22 A.M. RECEIPT# 58917
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEED
Compliance with
ACT 345, P.A. 1990

APPROVED ON: 6-6-99 JL
OAKLAND COUNTY REMONUMENTATION
PER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3				●									
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on March 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1823-GLO Wampler, D.S.; Set Post 10" White Oak N29°E 51 Links; 10" White Oak S80°E 93 Links
1.) 1974-Feldhauser, PS #10685; LCRC L.6409, Pg.474 - Fnd 1/2" Iron Rod
2.) 1993-Bonno, PS #32332; LCRC L.13268, Pg.100 - Fnd a 1" Pipe
3.) 1978-Ross, PS #19005; Unrecorded Survey - Object found not stated, no witnesses
4.) 1974-McCoy, PS #21270; Unrecorded Survey - Fnd 1/2" Iron
5.) 1987-Thompson, PS #23828; Unrecorded Survey - Fnd a 3/4" Pipe
6.) 1989-Bonno, PS #32332; Unrecorded Survey - Fnd 1/2" Pipe, used same wit as 1993 LCRC

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1" Iron Pipe located 6 feet South of the existing centerline of Cly Road extending to the East & West, which has a gravel surface. Old fence-tree row extending to the North & South.

Witnesses from LCRC #1, 2, Survey #7 & 9 were used to recover and verify the location of the found 1" Iron Pipe.

I accepted the found 1" Iron Pipe as the best evidence of the original corner position.

Field measurements see back side of LCRC

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-3 I replaced the found 1" Iron Pipe with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County
Remonumentation, PS #17623
N72°E 92.15' Set Mag Nail & Remon Washer SE face 19" Oak
N49°W 49.96' Set Mag Nail & Remon Washer NE face 8" Oak
S70°W 71.35' Set Mag Nail & Remon Washer NW face 32" Twin Oak
S18°W 31.76' Set Mag Nail & Remon Washer NW face 11" Oak



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 6-1-99