

SURVEY & REMONUMENTATION

MAY 24 2000

LIBER 20934 218

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

457111

For corners in

Oakland
(County)

Located in: Highland Township
Corner Code #

1. Public Land Survey	T <u>3</u> N	R <u>7</u> E	D <u>9</u>
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

LIBER 20934 PAGE 248
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
12/29/1999 02:40:59 P.M. RECEIPT# 110737
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with ACT 315, P.A. 1990
APPROVED ON: 11-24-99 JL
OAKLAND COUNTY REMONUMENTATION PER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on October 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4		3		2		1		
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set Post 8" Black Oak N50°E 1.78 chains; 9" White Oak N84°W 1.27 chains
1.) 1976-Hooth, PS #7966; LCRC L.6770, pgs.849 & 850 - Fnd a large pointed rock
2.) 1989-Bonno, PS #32332; LCRC L.10875, pg.052 - Fnd a 1/2" Re-rod
3.) 1993-Boss, PS #17022; LCRC L.13402, pg.445 - Fnd a 1/2" Iron Rod
4.) M.DOT Right of Way Map - Object found not staed, no witnesses
5.) 1988-Cornerstone Surveying & Eng., unrecorded Survey - Object found not stated, no witnesses
6.) 1989-Cornerstone Surveying & Eng., unrecorded Survey - Object found not stated, no witnesses
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 5/8" Iron Rod 25 feet South of the existing centerline of the West bound M-59 Highway extending to the East & West, which has a bituminous surface, also a old fence row extends to the North & South.

Witnesses from LCRC #2 & 3 were used to recover and verify the location of the found 5/8" Iron Rod.

I accepted the found 5/8" Iron Rod as the best evidence of the original corner position.

Field measurements see back side

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-9 I replaced the found 5/8" Iron Rod with a 4" diameter Concrete Monument with a 1/2" Iron Rod 36" from the center of the cap stamped Oakland County Remonumentation, PS #17623
Due North 129.07' Set Mag Nail & Remon Washer West face 40" Oak
N31°W 152.11' Set Mag Nail & Remon Washer NE face 24" Elm
N26°E 124.71' Set Mag Nail & Remon Washer SE face 11" Oak
S44°E 204.46' Set Mag Nail & Remon Washer NE face 36" Oak
N02°W 117.93' found 1/2" capped Iron Rod



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date 11-26-99