

MAY 24 2000

SECTION

LIBER 20934 250

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

457112

For corners in

LIBER 20934 PAGE 250
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
12/29/1999 02:41:01 P.M. RECEIPT# 110737
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Oakland (County) Located in: Highland Township Corner Code #
1. Public Land Survey T3N R7E E-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Compliance with Act 345, P.A. 1990
APPROVED ON: 11-24-99 JLB
OAKLAND COUNTY REMONUMENTATION
FFR GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column E and row 6.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set Post 36" White Oak N21 1/2 E 20 Links; 11" White Oak N79 1/2 W 25 Links
1.) 1972-Wilson, PS #13604; LCRC L. 5813, Pg.885 - Fnd a "T" Iron
2.) 1995-Thompson, PS #23828; LCRC L.15655, Pg.264 - Fnd a 1/2" Iron w/cap #15536
3.) 1995-Thompson, PS #23828; Survey L.15655, Pg.277 - Fnd a 1/2" Iron Road w/cap #15536, no witnesses (Con't on back side)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" capped Iron Rod #15536 located in the intersection of a fence & rock row extending to the North, South, East & West.

Witnesses from Survey #3 were used to recover and verify the location of the found 1/2" capped Iron Rod #15536.

I accepted the found 1/2" capped Iron Rod #15536 as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

E-5 to E-6

GLO = 40 chain sor 2640.00 Ft.
Sidwell W 1/2 Sec 16 (11-16) = 2630.39 Ft.
Unrecorded Survey by Raymond J. Kostecke, PS #12584 dated 8/20/84 = 2630.39 Ft.
Recorded Survey by Brad F. Thompson, PS #23828 dated 8/8/95 = 2629.61 Ft.
Unrecorded Survey by Grant Ward, PS #22445 dated 5/20/93 = 2629.68 Ft.
2629.56 Ft. (GPS-MEA)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-6 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
N30 W 18.00' Set Mag Nail & Remon Washer North face 38" Oak
N86 E 23.95' Set Mag Nail & Remon Washer North face 26" Oak
S27 E 31.15' Set Mag Nail & Remon Washer SW face 10" Maple
N86 W 52.25' Set Mag Nail & Remon Washer South face 27" Twin Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 11-26-99