

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
(County)

Located In: Highland Township

Corner Code #

LIBER 20329 PAGE 648
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
07/29/1999 11:46:39 A.M. RECEIPT# 58917
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CABELL, CLERK/REGISTER OF DEEDS

1. Public Land Survey

T3N R7E F-3

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

SURVEY & REMONUMENTATION

MAR 21 2000

SECTION

Compliance with ACT 345, P.A. 1990

APPROVED ON: 6-6-99 JK
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

I, Huston K. Kennedy, in a field survey on March 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1823-GLO Wampler, D.S.; Set Post 20" White Oak N26°E 79 Links; 12" White Oak S2 1/2°W 82 Links
 1.) 1990-Newman, PS #24607; LCRC L.11604, Pg.648 - Fnd 1/2" Re-rod
 2.) 1997-Kapelczak, PS #24598; LCRC L.17129, Pg.704 - Fnd 1/2" Re-rod
 3.) Kapelczak, PS #24598; Unrecorded Survey - Object found not stated, no witnesses
 4.) 1983-Bishop, PS #25829; Unrecorded Survey - Object found not stated, no witnesses
 5.) 1980-Feldhauser, PS #10685; Unrecorded Survey - Object found not sated, no witnesses
 6.) 1943-1948-Oakland County Road Commission Section Ties - Fnd Iron Pin

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod located in the existing centerline of Clyde Road extending to the East & West, which has a gravel surface. No lines of occupation.

Witnesses from LCRC #1 & 2 Unrecorded Witnesses #6 were used to recover and verify the location of the found 1/2" Iron Rod

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

F-3 to E-3

GLO = 40.59 1/2 chains or 2679.27 Ft.
Sidwell E 1/2 of NW 1/4 Sec 9 (11-9B) + W 1/2 of NW 1/4 of Sec 9 (11-9A) = 2683.06 Ft.
2682.37 Ft. (GPS-MEA)

F-3 to G-3

GLO = 40.59 1/2 chains or 2679.27 Ft.
Unrecorded Survey by Joseph Bishop, PS #25829 = 2688.12 Ft.
"HIGHLAND HILLS" + Parcels (Sec 9) = 2688.77 Ft.
2687.45 Ft. (GPS-MEA)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 F-3 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County
 Remonumentation, PS #17623
 N45°W 70.77' Set Mag Nail & Remon Washer SW face Power Pole
 S59°W 63.74' Set Mag Nail & Remon Washer NW face 27" Oak
 S16°E 31.21' Set Mag Nail & Remon Washer NE face 31" Oak
 S72°E 91.40' Set Mag Nail & Remon Washer NE face 33" Oak



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 6-1-99