

MAY 24 2000

LIBER 20934 266

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

457121

<u>Oakland</u> (County)	Located In: Highland Township	Corner Code # F-5
1. Public Land Survey	T <u>3</u> N R <u>7</u> E	F-5
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 20934 PAGE 266  
 \$9.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 12/29/1999 02:45:19 P.M. RECEIPT# 110738  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
 ACT 345, P.A. 1990

APPROVED ON: 8-31-99 JH  
 OAKLAND COUNTY REMONUMENTATION  
 PER GROUP COMMITTEE

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5						●							
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 1817-GLO Wampler, D.S.; Set Post 22" White Oak S82°E 4 Links  
 1.) 1980-Lippincott, PS #25855; LCRC L.7709, Pg.344 - Fnd a 1/2" Re-rod  
 2.) 1988-Bonno, PS #32332; LCRC L.10526, PG.824 - Fnd a 1/2" Re-rod in a Monument Box  
 3.) 1964-Cole, PS #4750; Unrecorded Survey - Object found not stated, no witnesses  
 4.) 1978-Feldhauser Associates; Unrecorded Survey - Object found not stated, no witnesses  
 5.) 1984-Kostecke & Associates; Unrecorded Survey - Object found not stated, no witnesses
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod in a Monument Box 3 feet South of the existing centerline of Middle Road extending to the East & West, which has a bituminous surface, also a tree-fence row extending to the South.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 1/2" Iron Rod in a Monument Box

I accepted the found 1/2" Iron Rod in a Monument Box as the best evidence of the original corner position

FIELD MEASUREMENTS BETWEEN

F-5 to E-5  
 GLO = 40.65 chains or 2682.90 Ft.  
 Sidwell E 1/2 Sec 16 (11-18) = 2701.61 Ft.  
 Sidwell E of SW 1/4 + W 1/2 of SW 1/4 Sec 9 (11-9F + 11-9E) = 2702.39 Ft.  
 2700.40 Ft. (GPS-MEA)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 F-5 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a existing Monument Box  
 N46°E 52.65' Set Mag Nail & Remon Washer SE face 8" Cedar  
 N31°W 126.65' Set Mag Nail & Remon Washer NW face 14" Pine  
 S63°W 94.45' Set Mag Nail & Remon Washer NW face 14" Walnut  
 S54°E 37.90' Set Mag Nail & Remon Washer NE face 12" Walnut

2P  
 R

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence the position of the original corner.

Signed by: [Signature]  
 Surveyor's Michigan License No. 17623

Date 8-1-99