

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 20934 PAGE 261
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
12/29/1999 02:44:39 P.M. RECEIPT# 110738
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland
(County)

Located in: Highland Township
Corner Code #

1. Public Land Survey T3N R7E F-7
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

4. Lot No. Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on May 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column G and row 7.

- A. Description of original monument and accessories and/or subsequent restoration:
1.) 1989-Bonno, PS #32332; LCRC L.11145, Pg.106 - Fnd a 1/2" Re-rod
2.) 1989-Bonno, PS #32332; Survey L.11145, Pg.105 - Fnd a 1/2" Re-rod, used same wit as 1989 LCRC
3.) 1908-Slater, County Surveyor; Unrecorded Survey - Object found not stated, no witnesses
4.) 1991-Smith, PS #33140; Unrecorded Survey - Object found not stated, no witnesses

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod 9 feet North of the existing centerline of Wardlow Road extending to the East & West, which has a gravel surface, also old fence, tree & rock row extending to the North & South

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

F-7 to E-7
GLO = 40.25 chains or 2656.50 Ft.
No sidwell or plat distances
2680.28 Ft. (GPS-MEA)

F-7 to G-7
GLO = 40.25 chains or 2656.50 Ft.
No plat or sidwell distances
Unrecorded Survey by F.A. Slater dated 5/15/08 (Sec 16) = 40.40 chains or 2669.04 Ft.
2664.82 Ft. GPS-MEA

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
F-7 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
N67°W 71.45' Set Mag Nail & Remon Washer NE face 22" Oak
N44°E 70.82' Set Mag Nail & Remon Washer NW face 27" Oak
S63°E 100.33' Set Mag Nail & Remon Washer North face 30" Oak
S17°E 72.87' Set Mag Nail & Remon Washer West face 12" Poplar

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 11-4-99

