

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

273052

For corners in

Oakland
(County)

Located In: Highland Township
Corner Code #

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. Recorded Plat
5. Private Claims

T3N R7E G-1
T R SURVEY &
T R
T R
S T R
S T R
S T R
SECTION

LIBER 20329 PAGE 87
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
07/29/1999 11:41:06 A.M. RECEIPT# 58913
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990
APPROVED ON: 4-27-99 JK
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked in cell G-1.

I, Huston K. Kennedy, in a field survey on March 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: 1815-1816-GLO Holmes, D.S.; No post was set, corner falls in a lake
1.) 1979-Finney, PS #15536; LCRC L.7580, Pg.809 - Fnd a 1/4" square Iron (not for this corner)
2.) Albright, PS #10057; Unrecorded Survey - Object found not stated, no witnesses
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner has not been perpetuated, the corner falls in Highfield Lake. The unrecorded survey by John D. Albright, PS #10057 depicted the corner as being in Highfield Lake. The calculated position of the inaccessible corner was 4.66 feet South of the town line, and the final position of the corner was calculated to be on the town line. A meander corner was set on the town line 120.00 feet West of the calculated position of this corner. Corner common to Sections 33 & 34, T4N, R7E, Rose Township (G-13) is located 91.22 feet to the East.

FIELD MEASUREMENTS BETWEEN

G-1 to F-1
No GLO (G-1 falls in a lake)
Sidwell (E 1/4 Sec 4) = 2674.33 Ft.
2674.33 Ft. (GPS-CAL)

G-1 to G-2
GLO = 46.10 chains or 3042.60 Ft.
Unrecorded Survey by John J. Albright, PS #10057 = 3022.47 Ft.
3022.47 Ft. (GPS-CAL) & 3027.12 Ft. (GPS-CAL) set the corner on the town line

G-1 to G-13
No GLO - (G-1 & G-13 corner falls in a lake)
91.22 Ft. (GPS-CAL)
G-1 to H-1
No GLO (G-1 falls in a lake)
North part of W 1/2 Sec 3 (11-3N) = 2588.99 Ft.
2589.04 Ft. (GPS-CAL)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: G-1 I set a 4" diameter Concrete Monument with 1/2" Iron Rod 36" long w/2" diameter brass cap stamped G-1. Remonumentation, PS #17623 as a meander corner on the town line 120.00 feet East of G-1.
N15°E 19.90' Set Mag Nail & Remon Washer East face 20" Ash
S70°W 12.35' Set Mag Nail & Remon Washer SE face 10" Oak
S29°W 23.03' Set Mag Nail & Remon Washer East face 20" Maple
S23°E 15.08' Set Mag Nail & Remon Washer NE face 18" Poplar
East 211.22' Corner common to Sections 33 & 34, T4N, R7E, Rose Township (G-13)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 4-30-99