

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
(County)

Located in:
Highland Township

Corner Code #

38631

1. Public Land Survey

T3N R7E G-6

2. Property Controlling
in Section

S T R
S T R
S T R
S T R

3. Miscellaneous
Property in Sec.

SECTION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

LIBER 21077 PAGE 435
\$7.00 NISE RECORDING
\$2.00 REMONUMENTATION
02/08/2000 09:02:32 A.M. RECEIPT# 10181
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CABELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-16-99 SK
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1823-GLO Wampler, D.S.; Set Post 10" Black Oak S71°E 2.66 chains; 26" White Oak N74°W 2.75 chains
1.) 1989-Kostecke, PS #12584; Unrecorded Survey - Fnd a Iron Rod
2.) 1990-Kostecke, PS #12584; Unrecorded Survey - Fnd a Iron Rod, used same wit as 1989 Survey
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1" Iron Pipe w/caps #19836 & 12663, a tree-rock row extending the South and a Detroit Edison Power Line extending to the East.

Witnesses from unrecorded Survey #1 were used to recover and verify the location of the found 1" Iron Pipe w/caps #19836 & 12663.

I accepted the found 1" Iron Pipe w/caps #19836 & 12663 as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

G-6 to G-5

GLO = 40 chains or 2640.00 Ft.
No sidwell or plat distances
Unrecorded Survey by Raymond J. Kostecke, PS #12584 dated 2/21/90 (Sec 15) = 2661.11 Ft. (CAL)
2640.31 Ft. (GPS-MEA)

G-6 to G-7

GLO = 40 chains or 2640.00 Ft.
Sidwell W 1/4 Sec 15 (11-15) = 2652.11 Ft.
2650.97 Ft. (GPS-MEA)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-6 I replaced the found 1" Iron Pipe w/caps #19836 & 12663 with a 4" diameter Concrete Monument with a 1/2" Iron Rod 3 long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
Due South 54.20' Set Mag Nail & Remon Washer West face 40" Poplar
N16°E 1.75' Set Mag Nail & Remon Washer SE face Power Pole
N17°E 30.75' SW corner of house #2300
S85°W 56.65' NE corner of house #2266

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence the position of the original corner.

Signed by: [Signature]

Date 12-16-99

Surveyor's Michigan License No. 17623

