

SURVEY & REMONUMENTATION

MAY 24 2000

LIBER 20934 PAGE 270

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

457123

For corners in

Oakland
(County)

Located in:
Highland Township

Corner Code #

- | | | | |
|------------------------------------|-----|-----|-----|
| 1. Public Land Survey | T3N | R7E | G-7 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |
4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

LIBER 20934 PAGE 270
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
12/29/1999 02:45:19 P.M. RECEIPT# 110738
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

APPROVED BY: 11-3-99 JH
OAKLAND COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on May 6, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set Post 14" White Oak N38°E 1.40 Chains; 16" White Oak N47°W 1.54 Chains
- 1.) 1990-Ward, PS #22445; LCRC L.11626, Pg.286; - Fnd a Angle iron
 - 2.) 1908-Slater, County Surveyor; unrecorded Survey - Object found not stated, no witnesses
 - 3.) 1966-McGinnis, PS #11111; unrecorded Survey - Object found not stated, no witnesses
 - 4.) 1977-Kostecke, PS #12584; unrecorded Survey - Object found not stated, no witnesses
 - 5.) 1979-Kostecke, PS #12584; unrecorded Survey - Object found not stated, no witnesses

(Con't on back side)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a Angle Iron in the existing centerline of Wardlow Road extending to the West, which has a gravel surface, and extending to the East, which has a bituminous surface, also a tree, fence & rock row extending to the North & South.

Witnesses from LCRC #1 were used to recover and verify the location of the found Angle Iron.

I accepted the found Angle Iron as the best evidence of the original corner position.

Field measurements see back side

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-7 I replaced the found Angle Iron with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped O.K. Kennedy
Remonumentation, PS #17623
N02°E 31.92' Set Mag Nail & Remon Washer East face 23" Box Elder
N72°W 115.10' Set Mag nail & Remon Washer South face 14" Hickory
S63°W 60.82' Set Mag Nail & Remon Washer North face 32" Oak
S57°E 80.48' Set Mag Nail & Remon Washer North face 39" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 017623

Date 11-4-99

