

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

51124

LIVER 21118 PAGE 118
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/18/2000 10:03:11 A.M. RECEIPT# 13978
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland
(County)

Located in:
Highland Township

Corner Code #

1. Public Land Survey

T3N R7E G-8

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

SECTION

APPROVED ON
12-7-99 JH
OAKLAND COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on October 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set Post 6" Black Oak N37°W 1.01 chains; 14" Black Oak N70°E 3.18 chains
1.) 1972-Jones, PS #16045; LCRC L.5974, pgs.614 & 615 and L.5975, pg.333 - Set a 1/2" Iron Rod
2.) 1974-Albright, PS #10057; LCRC L.6373, pg.870 - Fnd a 1/2" Re-rod
3.) 1983-Wizynajty, PS #21585; LCRC L.8550, pg.388 - Fnd a 1/2" Iron Re-rod
4.) 1989-Donnelly, PS #21663; LCRC L.11062, pg.235 - Fnd a 1/2" Iron Rod w/caps, #6694, 10791 & 10045
5.) Unrecorded survey, surveyor unknown, object found not stated, no witnesses
6.) Right of Way Map, object found not stated, no witnesses
7.) 1927-Baldwin, PS #1298; unrecorded survey, book 33, pg.18 - Object found not stated, no witnesses
8.) 1991-Stephens, PS #29252; unrecorded survey - Fnd a 1/2" Re-rod, used same wit as 1974 LCRC

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod w/cap located in a old tree, fence & rock ro extending to the North, South & West.

Witnesses from LCRC #2 & 3 were used to recover and verify the location of the found 1/2" Iron Rod w/cap.

I accepted the found 1/2" Iron Rod w/cap as the best evidence of the original corner position.

Field measurements back side of LCRC

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-8 I replaced the found 1/2" Iron Rod with a 4" diameter Concrete Monument with a 1/2" Iron Rod 1/2" long 1 1/2" diameter. Brass cap stamped Oakland County Remonumentation, PS #17623
Due North 27.20' Set Mag Nail & Remon Washer West face 12" Oak
Due East 23.10' Set Mag Nail & Remon Washer South face 10" Pine
Due South 26.00' Set Mag Nail & Remon Washer East face 25" Oak
Due West 28.95' Set Mag Nail & Remon Washer South face 12" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 2-10-2000



LIBER 21118 - 119

SURVEY &
RECORDS DIVISION

MAR 21 2000

FIELD MEASUREMENTS BETWEEN

G-8 to G-7

SECTION

GLO = 40 chains or 2640.00 Ft.
Sidwell W ½ Sec 22 (11-22) = 2654.21 Ft.
Unrecorded Survey = 2654.22 Ft.
M.DOT Right of Way Map = 2651.15 Ft.
2653.09 Ft. (GPS-MEA)

G-8 to G-9

GLO = 40 chains or 2640.00 Ft.
"SUPERVISOR'S PLAT NO. 4" + "MAE-GRACE ACRES" + Parcel (Sec 22) = 2660.22 Ft.
M.DOT Right of Way Map = 2651.18 Ft.
2657.72 Ft. (GPS-MEA) to pt. #746)