

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

273055

For corners in

Oakland (County)

Located In: Highland Township Corner Code #

1. Public Land Survey

T3N R7E I-1

2. Property Controlling in Section

S T R Survey & RE-ESTABLISHMENT

3. Miscellaneous Property in Sec.

S T R MAR 21 2000

SECTION

4. Lot No. Recorded Plat
5. Private Claims

LIBER 20329 PAGE 90
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
07/29/1999 11:41:06 A.M. RECEIPT# 58913
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 4-27-99 JIK
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, Huston K. Kennedy in a field survey on March 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column I and row 1.

- A. Description of original monument and accessories and/or subsequent restoration: 1815-1817-GLO Holmes, D.S.; Set Post 8" White Oak S40°W 25 Links; 11" White Oak S63°E 64 Links; 1.) 1988-Bonno, PS #32332; LCRC L.10526, Pg.829 - Fnd a 1" Pipe
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1" Iron Pipe located 110 feet West of the existing centerline of Milford Road and extends to the North & South, which has a bituminous surface. A tree-fence row extends to the East & West. The corner as found is 7.69 feet South of the township line and was reset on the town line. Corner common to Sections 34 & 35, T4N, R7E, Rose Township (I-13) and is located 189.34 feet to the East.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1" Iron Pipe.

I accepted the found 1" Iron Pipe as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

I-1 to H-1
No GLO
No sidwell or plat distances
2600.29 Ft. (GPS-MEA)

I-1 to I-13
GLO = 2.85 chains or 188.10 Ft.
189.34 Ft. (GPS-MEA)

I-1 to I-2
GLO = 47.12 chains or 3109.92 Ft.
Sidwell (W 1/2 Sec 2) = 3120.25 Ft.
3118.25 Ft. (GPS-MEA) & 3125.94 Ft. (GPS-MEA) reset on the town line

I-1 to J-1
No GLO
Sidwell (W 1/2 Sec 2) = 2812.02 Ft.
2811.77 Ft. (GPS-MEA)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: I-1 I set a 4" diameter Concrete Monument with 1/2" Iron Rod 36" long w/2" diameter brass cap stamped with 'HUSTON KENNEDY' Remonumentation, PS #17623 on the town line
N20°E 8.75' Set Mag Nail & Remon Washer NW face 12" Ash
N16°W 11.02' Set Mag Nail & Remon Washer NE face 9" Cherry
S65°W 20.45' Set Mag Nail & Remon Washer SE face 41" Oak
S11°W 51.04' Set Mag Nail & Remon Washer West face 33" Oak
East 189.34 feet, corner common to Sections 34 & 35, T4N, R7E, Rose Township (I-13)



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 4-30-99