

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

345422

Oakland  
 (County)

Located In: Highland Township  
 Corner Code #

LIBER 20560 PAGE 500  
 \$7.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 09/20/1999 08:43:23 A.M. RECEIPT# 79775  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

1. Public Land Survey T2N R9E I-2  
 T R  
 T R  
 T R  
 2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R

SECTION

Compliance with  
 ACT 345, P.A. 1990  
 APPROVED ON: 8-9-99 JN  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3	●	2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Huston K. Kennedy, in a field survey on March 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 1823-GLO Wampler, D.S.; Set Post 9" White Oak N04°E 31 Links; 7" White Oak S61 1/2°W 98 Links  
 1.) 1988-Bonno, PS #32332; LCRC L.10526, Pg.829 - Fnd a PK Nail  
 2.) 1979-Heil, PS #18893 Unrecorded Survey - Object found not stated, no witnesses  
 3.) 1981-Kostecke, PS #12584; Unrecorded Survey - Object found not stated, no witnesses  
 4.) 1981-Kostecke, PS #12584; Unrecorded Survey - Object found not stated, no witnesses  
 5.)  
 B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a PK Nail located 8 feet East of the existing centerline of Milford Road extending to the North & South, which has a bituminous surface.

Witnesses from LCRC #1 were used to recover and verify the location of the found PK Nail.

I accepted the found PK Nail as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

I-1 to I-2

GLO = 47.12 chains or 3109.92 Ft.  
 Sidwell (W 1/2 Sec 2) = 3120.25 Ft.  
 3118.25 Ft. (GPS-MEA) & 3125.94 Ft.  
 (GPS-MEA) reset on the town line

I-2 to I-3

GLO = 40 chains or 2640.00 Ft.  
 Unrecorded Survey by Raymond J. Kostecke, PS #12584 Dated 6/1/82  
 Sidwell (W 1/2 Sec 2) = 2638.55 Ft.  
 2638.70 Ft. (GPS-MEA)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 I-2 I replaced the found PK Nail with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a new Monument Box  
 S42°E 51.80' Set Mag Nail & Remon Washer SE face 50" Oak East 33.05 feet, found 1/2" Iron Rod  
 S44°E 25.20' Set Mag Nail & Remon Washer SW face 13" Oak  
 N53°W 48.35' Set Mag Nail & Remon Washer NE face 32" Oak  
 N85°E 16.20' Set Mag Nail & Remon Washer South face 28" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Huston K. Kennedy  
 Surveyor's Michigan License No. 17623

Date 8-5-99