

SURVEY & REMONUMENTATION

MAY 24 2000

LIBER 20560 PAGE 501

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

345424

For corners in

Oakland
(County)

Located in:
Highland Township

Corner Code #

- | | | | |
|------------------------------------|---|---|-----|
| 1. Public Land Survey | T | R | 1-3 |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling In Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

LIBER 20560 PAGE 501
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
09/20/1999 08:43:31 A.M. RECEIPT# 79775
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 9-4-99 JH
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on March 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3									●				
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1823-GLO Wampler, D.S.; Set Post 11" White Oak S89°W 1.92 chains; 9" White Oak S88°E 2.31 chains
1.) 1974-Stonerock, PS #13601; LCRC L.6405, Pg.380 - Fnd a PK Nail over a bent Iron
2.) 1980-Lippincott, PS #25855; LCRC L.7743, Pg.33 - Fnd a 1/2" Re-rod
3.) 1987-Ward, PS #22445; LCRC L.9912, Pg.532 - Fnd a Iron Rod
4.) 1993-Thompson, PS #23828; LCRC L.13496, Pg. 303 - Fnd a Iron Rod
5.) 1926-Baldwin; Unrecorded Survey - Set an Iron Pipe, no witnesses
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod located in the existing centerline of Milford Road extending to the North & South, which has a bituminous surface, also in the existing centerline of White Lake Road extending to the East & West, which has a gravel surface.

(Con't on back side of LCRC)

Witnesses from LCRC #1, 2, 3, 4, and unrecorded Surveys #9, 10 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

Field measurements on back side of LCRC

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-3 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped
Remonumentation, PS #17623
N34°W 117.00' NE corner of house #5181
N46°E 69.60' Set Mag Nail & Remon Washer NW face Guide Pole
S46°W 80.05' Set Mag Nail & Remon Washer SE face Guide Pole
S43°E 76.34' Set Mag Nail & Remon Washer SW face 27" Oak



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 8-5-99