

SURVEY & REMONUMENTATION

MAY 24 2000

LIBER 20934 274

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

457125

corners in

<u>Oakland</u> (County)	Located In: Highland Township	Corner Code #	
Public Land Survey	T3N	R7E	I-5
	T	R	
	T	R	
	T	R	
Property Controlling Section	S	T	R
	S	T	R
Miscellaneous	S	T	R
Property in Sec.	S	T	R

LIBER 20934 PAGE 274
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
12/29/1999 02:45:19 P.M. RECEIPT# 110738
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

In compliance with
ACT 74, P.A. 1990

APPROVED ON: 11-2-99 *sh*
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Lot No. _____ Recorded Plat _____
Private Claims _____

Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under provisions of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, verified, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Description of original monument and accessories and/or subsequent restoration:

- 1823-GLO Wampler, D.S.; Set Post 12" White Oak S14 1/2°W 12 Links; 12" White Oak S43°E 80 Links
- 1.) 1972-Jones, PS #16045; LCRC L.5974, Pg.614 - Fnd a 5/8" Re-rod in a Monument Box
- 2.) 1962-Oakland County Road Commission unrecorded witnesses - Fnd a rod in Wardlow Road
- 3.) 1989-Bonno, PS #32332; Unrecorded Survey - Object found not stated, no witnesses

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 3/4" Iron Rod in a Monument Box in existing centerline of Harvey Lake Road extending to the North & South, which has a bituminous surface, 30 feet North of the existing centerline of Lake View Drive extending to the West, which has a gravel surface, also a tree, fence & rock row extending to the East.

Witnesses from LCRC #1 were used to recover and verify the location of the found 3/4" Iron Rod in a Monument Box.

I accepted the found 1/2" Iron Rod in a Monument Box as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

I-5 to H-5
No GLO, corner falls in a lake
No plat or sidwell distances
2658.84 Ft. (GPS-MEA)

I-5 to I-6
GLO = 40 chains or 2640.00 Ft. (corner falls in lake)
"WALING WOODS" (Sec 15) = 2660.44 Ft.
Unrecorded Survey by Gilbert G. Bonno, PS #32332 dated 11/1/89 = 2660.26 Ft.
2170.12 Ft. (I-5 to meander corner)
2660.44 Ft. (CAL)

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-5 I replaced the found 3/4" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a existing Monument Box
Due West 61.66' Set Mag Nail & Remon Washer South face Power Pole
N32°W 69.32' Set Mag Nail & Remon Washer NE face 10" Maple
N86°E 58.22' Set Mag Nail & Remon Washer North face Power Pole
S37°E 162.87' Set Mag Nail & Remon Washer SW face Power Pole



(Cont' on back)

2p
R

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Accepted by: *H. Kennedy*
Surveyor's Michigan License No. 17623

Date 11-11-99