

SURVEY & REMONUMENTATION

MAY 24 2000

LIBER 20934 254

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

457114

or corners in

<u>Oakland</u> (County)	Located In: Highland Township	Corner Code # I-6
Public Land Survey	T <u>3N</u> R <u>7E</u>	<u>I-6</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

LIBER 20934 PAGE 254
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
12/29/1999 02:41:01 P.M. RECEIPT# 110737
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-2-99 SH
OAKLAND COUNTY REMONUMENTATION
PLAT GROUP COMMITTEE
Register of Deeds Stamp & File Number

Lot No. _____ Recorded Plat _____
Private Claims _____

Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, discovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15	●	14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; No post was set, no witnesses, corner falls in a lake
1973-Kostecke, PS #12584; unrecorded Survey - Object found not stated, no witnesses
- Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - corner falls in a Leonard Lake. "WAILING WOODS" shows a meander corner being set on the East line of Section 15 that is located 2170.15 feet South of I-5. I found a 1/2" capped Iron Rod located as shown on "WAILING WOODS" 27 feet ± North of the waters edge of Leonard lake.

FIELD MEASUREMENTS BETWEEN

I-6 to I-5
No GLO, corner falls in Leonard Lake
"WAILING WOODS" (Sec 15) = 2660.44 Ft.
2170.15 Ft. (I-5 to meander corner on the North side of Leonard Lake)
2660.44 Ft. (CAL)

I-6 to I-7
No GLO, corner falls in Leonard Lake
Unrecorded Survey by Raymond Kostecke, PS #12584 dated 11/29/73 (Sec 14) = 2625.40 Ft.
1987.79 Ft. (I-7 to meander corner of South side of Leonard Lake)
2627.09 Ft. (CAL)

- Description of monument for corner and accessories established to perpetuate locating the position of the meander corner on the back side of LCRC:
I-6 I set a 4" diameter Concrete Monument with a 1/2" Iron Rod 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 on the line between Sections 14 & 15 on the North side of Leonard Lake as a meander corner to I-6

S31°E 24.00' Set Mag Nail & Remon Washer NE face 10" Tamarack
S84°E 20.03' Set Mag Nail & Remon Washer North face 9" Birch
N80°E 3.20' Set Mag Nail & Remon Washer NW face 11" Birch
N47°W 18.04' Set Mag Nail & Remon Washer SW face 10" Birch
South 490.32 feet to I-6, which is inaccessible corner

Con't on back side

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: Huston K. Kennedy Date 11-26-99
Surveyor's Michigan License No. 17623