

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

38636

LIBER 21077 PAGE 442
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/08/2000 09:04:09 A.M. RECEIPT# 10181
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEE

For corners in

Form with fields for County (Oakland), Located In (Highland Township), Corner Code # (J-9), and numbered sections 1-5 for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

Compliance with ACT 345, P.A. 1990
APPROVED ON: 1-12-2000 J/K
OAKLAND COUNTY REMONUMENTATION PERMANENT COMMITTEE

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13, containing numerical values from 1 to 36.

I, Huston K. Kennedy, in a field survey on October 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: 1817-GLO Wampler, D.S.; Set Post 8" Black Oak S29°E 14 Links; 10" Black Oak N12 1/2°E 15 Links
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod 2 feet South of the existing centerline of Livingston Road extending to the East & West, which has a gravel surface.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

J-9 to I-9
GLO = 39.845 chains or 2629.77 Ft.
No sidwell or plat distances
2627.07 Ft. (GPS-MEA)
2627.40 Ft. (EDM)

J-9 to K-9
GLO = 39.845 chains or 2629.77 Ft.
No sidwell or plat distances
2647.73 Ft. (GPS-MEA)

J-9 to J-11
No GLO
Unrecorded Survey Grant dated 1/10/85 = 5316.46 Ft.
5315.35 Ft. (GPS-MEA)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: J-9 I replaced the found 1/2" Iron Rod with 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
N03°E 23.00' Set Mag Nail & Remon Washer West face 30" Oak
S54°E 51.56' Set Mag Nail & Remon Washer SW face 34" Oak
S67°E 75.57' Set Mag Nail & Remon Washer NW face 31" Oak
S07°E 35.56' Set Mag Nail & Remon Washer West face 8" Pine

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 12-19-99