

MAY 24 2000

LIBER 20329PG652

273084

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 20329 PAGE 652
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
6/7/29/1999 11:47:06 A.M. RECEIPT# 58917
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

<u>Oakland</u> (County)	Located In: Highland Township	Corner Code #
1. Public Land Survey	T3N R7E	K-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with ACT 345, P.A. 1990
APPROVED ON: 6-6-99 J/K
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on March 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1815-1816 GLO Holmes, D.S.; Set Post 4" Black Oak S4°E 18 Links; 36" White Oak S63 1/2°W 74 Links
- 1976-Stonerock, PS #13601; LCRC L.6748, Pg.613 - Fnd 1/2" Iron
 - 1966-Roskelly, PS #?; Unrecorded Survey - Object found not stated, no witnesses
 - 1970-Finney & Kostecke, Inc.; Unrecorded Survey - Object found not stated, no witnesses
 - 1971-Finney & Kostecke, Inc.; Unrecorded Survey - Object found not stated, no witnesses
 - 1971-William C. ?, PS #?; Unrecorded Survey - Object found not stated, no witnesses
 - 1976-Stonerock, PS #13601; Unrecorded Survey - Fnd 1/2" Iron Rod, no witnesses
 - 1977-Stonerock, PS #13601; Unrecorded Survey - Fnd 1/2" Iron Rod, used same wit as 1976
 - 1978-Kieft Engineering, Inc., Unrecorded Survey - Fnd a 1" Pipe
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron 2 feet North of the existing centerline of Doty Road extending to the East & West, which has a gravel surface. The corner as found is 2.70 feet North of the town line and was reset on the town line. Corner common to Sections 35 & 36, T4N, R7E, Rose Township (K-13) is located 176.61 feet to the East.



Witnesses from LCRC #1 & Survey #8 were used to recover and verify the location of the found 1/2" Iron.

I accepted the found 1/2" Iron as the best evidence of the original corner position.

Field measurements see back side of LCRC

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-1 I set a 4" diameter Concrete Monument with a 1/2" x 36" long Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 on the town line
N61°E 29.78' Fnd Mag Nail & Remon Washer stamped O.C.R. PS #31606 in NW face 44" Oak
S17°W 13.04' Fnd Mag Nail & Remon Washer stamped O.C.R. PS #31606 in East face 11" Hickory
N51°W 42.50' Fnd Mag Nail & Remon Washer stamped O.C.R. PS #31606 in NW face 26" Oak
S22°E 19.78' Set Mag Nail & Remon Washer NE face 15" Oak
East 176.61' corner common to Sections 35 & 36, T4N, R7E, Rose Township (K-13)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 6-1-99