

LIBER 20329 PAGE 654

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

273085

For corners in

Oakland
(County)

Located In: Highland Township Corner Code #

1. Public Land Survey

T3N R7E K-2

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____ Recorded Plat _____ SECTION _____
5. Private Claims _____

LIBER 20329 PAGE 654
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
07/29/1999 11:47:15 A.M. RECEIPT# 58917
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CABBELL, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 6-6-99 JK
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on March 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
1823 GLO Wampler, D.S.; Set Post 13" White Oak S46°W 84 Links; 15" White Oak S75°E 23 Links
1.) 1980-Williams, PS #25880; Unrecorded Survey - Fnd a 1/2" Bar.
2.) 1987-Kostecke, PS #12584; Unrecorded Survey - Object found not stated, no witnesses

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod located in a old tree-fence row extending to the North & South.

Witnesses from unrecorded Survey #1 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

K-2 to K-1

GLO = 48.08 chains or 3173.28 Ft.
Unrecorded Survey by Raymond J. Kostecke, PS #12584 dated 9/8/67 = 3176.57 Ft.
3174.91 Ft. (GPS-MEA)

K-2 to K-3

GLO = 40 chains or 2640.00 Ft.
Unrecorded Survey by Daniel Williams, PS #25880 dated 10/27/80 = 2633.60 Ft.
2638.24 Ft. (GPS-MEA)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-2 I replaced the found 1/2" Iron Rod with a 4" diameter Concrete Monument with 1/2" Iron Rod 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
N71°W 22.20' Set Mag Nail & Remon Washer North face 8" Oak
Due North 45.63' Set Mag Nail & Remon Washer West face 44" Oak
S31°E 32.45' Set Mag Nail & Remon Washer SW face 10" Oak
Due South 21.70' Set Mag Nail & Remon Washer East face 10" Cherry

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 6-1-99

