

SURVEY & REMONUMENTATION

MAY 24 2000

LIBER 20934 278

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

457127

for corners in

LIBER 20934 PAGE 278  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
12/29/1999 02:45:19 P.M. RECEIPT# 110738  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Oakland Located in: Corner Code #  
(County) Highland Township

1. Public Land Survey	T3N	R7E	K-6
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Compliance with  
ACT 345, P.A. 1990

APPROVED: 11-2-99 Jh  
OAKLAND COUNTY REMONUMENTATION  
LEADER GROUP COMMITTEE

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 20, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
1817-GLO Wampler, D.S.; Set Post 18" White Oak S82°E 2.59 chains; 12" Black Oak N12 1/2°E 2.46 chains  
1.) 1976-Hooth, PS #7966; LCRC L.6770, pg.857 - Fnd a 1/2" Iron  
2.) 1977-Albright, PS #10057; LCRC L.7007, pg.259 - Fnd a 3/8" Iron in Concrete  
3.) 1989-Thompson, PS #23828; LCRC L.10771, pg.200 - Fnd a 1/2" Iron  
4.) 1994-Thompson, PS #23828; LCRC L.14836, pg.466 - Fnd a 1/2" Iron Rod in a Monument, used same wit as 1989 LCRC  
(Con't on back side)
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod in a Monument Box 9 feet North of the existing centerline of Wardlow Road extending to the East & West, which has a bituminous surface, also a fence-free row extending to the North & South.

Witnesses from LCRC #1, 2 3, 4 and the monumentation as found in "SOUTH SHORES" were used to recover and verify the location of the found 1/2" Iron Rod in a Monument Box.

I accepted the found 1/2" Iron Rod in a Monument Box as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

K-6 to K-5  
GLO = 40 chains or 2640.00 Ft.  
Sidwall W 1/2 of NW 1/4 Sec 13 (11-13A) = 2632.99 Ft.  
Unrecorded Survey by Edwin C. Sage, Jr. PS #1583 (Sec 14) = 2633.00 Ft.  
"SOUTH SHORES" = 2633.00 Ft.  
2632.75 Ft. (GPS-MEA)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
K-6 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in the existing Monument Box  
Due North 27.85' Set Mag Nail & Remon Washer West face 26" Oak  
S02°E 60.65' Set Mag Nail & Remon Washer West face 21" Oak  
N38°W 44.65' Set Mag Nail & Remon Washer SW face 14" Oak  
S46°W 61.15' Set Mag Nail & Remon Washer NW face 16" Oak  
North 33.02 feet found 4" diameter Concrete Monument

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature] Date 11-3-99  
Surveyor's Michigan License No. 17623