

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

38638

or corners in

Oakland
(County)

Located In:
Highland Township

Corner Code #

Public Land Survey

Property Controlling
in Section

Miscellaneous

Property in Sec.

	T3N	R7E	K-9
	T	R	
	T	R	
	T	R	
S	T	R	SURVEY &
S	T	R	REMONUMENTATION
S	T	R	
S	T	R	MAR 21 2000

LIBER 21077 PAGE 443
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/08/2000 09:04:18 A.M. RECEIPT# 10181
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Lot No. _____ Recorded Plat _____ SECTION _____
Private Claims _____

Register of Deeds Stamp & File Number

Huston K. Kennedy, In a field survey on October 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or at the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, covered, found as expressed below:

OTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	5		5		4		3		2				1
3													
4	7		8		9		10		11				12
5													
6	18		17		16		15		14				13
7													
8	19		20		21		22		23				24
9													
10	30		29		28		27		26				25
11													
12	31		32		33		34		35				36
13													

Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 4" Pin Oak N38 1/2°W 74 Links; 4" Pin Oak S50 1/2°W 72 Links
- 1.) 1976-Hooth, PS #7966; LCRC L.6770, pg. 863 & 864 - Fnd a 3/4" Iron Rod
- 2.) 1982-Bissell, PS #18655; LCRC L.8243, pg.120 - Fnd a 1/2" Iron Rod & set a 1" Iron Pipe w/plastic cap #18655
- 3.) 1985-Ward, PS #22445; LCRC L.8885, pgs.508 & 509 - Fnd a 1" Iron Pipe w/cap
- 4.) 1990-Ward PS #22445; LCRC L.11628, pgs.292 & 293 Fnd a 1" Iron Pipe
- 5.) M.D.N.R. unrecorded Survey - Fnd a 1/2" Iron Rod & set a 1" Iron Pipe w/plastic cap, used same wit as 1982 LCRC
- 6.) 1962-Oakland County Road Commission unrecorded witnesses - Fnd a Iron Pipe

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod inside a 1" Iron Pipe located 5 feet South of the existing centerline of Livingston Road extending to the East & West, which has a gravel surface, and in the existing centerline of Waterbury Road extending to the North, which has a gravel surface, with an old fence row extending to the South. Also found a 1/2" Iron Rod 3.64 feet to the West, which I did not accept.

Witnesses from LCRC #2, 3 & unrecorded Survey #5 were used to recover and verify the location of the found 1/2" Iron Rod inside a 1" Iron Pipe.

I accepted the found 1/2" Iron Rod inside a 1" Iron Pipe as the best evidence of the original corner position.

Field measurements see back side

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-9 I replaced the found 1/2" Iron Rod inside a 1" Iron Pipe with a 5/8" x 24" Iron Rod w/2" diameter Brass cap.

- Oakland County Remonumentation, PS #17623
- N43°E 62.90' Set Mag Nail & Remon Washer NW face 9" Cherry
- S80°E 54.63' Set Mag Nail & Remon Washer North face 34" Poplar
- N23°W 69.15' Set Mag Nail & Remon Washer SW face 32" Oak
- S77°W 98.64' Set Mag Nail & Remon Washer North face 25" Black Walnut
- West 3.64' found 1/2" Iron Rod

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Accepted by: [Signature]
Surveyor's Michigan License No. 17623

Date 12-17-99



FIELD MEASUREMENTS BETWEEN

K-9 to J-9

GLO = 39.45 chains or 2629.77 Ft.
No sidwell or plat distances
2647.73 Ft. (GPS-MEA)

SURVEY &
RECORRENTATION

MAR 21 2000

SECTION

K-9 to K-8

GLO = 40 chains or 2640.00 Ft.
No sidwell or plat distances
2640.60 Ft. (GPS-MEA)
2641.07 Ft. (EDM-MEA)

K-9 to K-10

GLO = 40 chains or 2640.00 Ft.
Unrecorded Survey by Donald Bissell, PS #18655 for MD.N.R. dated 2/9/83 (Sec 25) = 2642.06 Ft.
2642.53 Ft. (GPS-MEA)

K-9 to L-9

GLO = 40.75 chains or 2689.50 Ft.
Unrecorded Survey by Donald Bissell, PS #18655 for M.D.N.R. dated 2/9/83 (Sec 25) = 2680.40 Ft.
2680.32 Ft. (GPS-MEA)