

LIBER 20329 PG 655

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland  
(County)

Located In: Highland Township  
Corner Code #

1. Public Land Survey

T3N R7E L-1

T R

T R

T R

2. Property Controlling in Section

S T R SURVEY & RECONSTRUCTION

3. Miscellaneous Property in Sec.

S T R

S T R

MAR 21 2000

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

273086

LIBER 20329 PAGE 655  
\$7.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
07/29/1999 11:47:17 A.M. RECEIPT# 58917  
PAID RECORDED - OAKLAND COUNTY  
S. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 6-6-99 JKL  
OAKLAND COUNTY REMONUMENTATION  
PEER REVIEW COMMITTEE

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on January, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1817-GLO Holmes, D.S.; No post was set, no witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner has not been perpetuated and was recovered based upon the property description for Parcels 11-01-201-001 & 11-01-201-002. The South 1/4 corner of Section 36, T4N, R7E, Rose Township is located 127.47 feet to the West.

**FIELD MEASUREMENTS BETWEEN**

L-1 to K-1  
No GLO  
No recorded position  
2942.21 Ft. (GPS-MEA)

L-1 to M-1  
No GLO  
No recorded distances  
2533.83 Ft. (GPS-MEA)

L-1 to L-13  
No GLO  
127.47 Ft. (GPS-MEA)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
L-1 I set a 4" diameter Concrete Monument with a 1/2" x 36" long Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 on the town line  
S62°W 21.68' Set Mag Nail & Remon Washer North face 32" twin Hickory  
N02°W 29.24' Set Mag Nail & Remon Washer West face 34" Oak  
N86°E 6.10' Set Mag Nail & Remon Washer South face 27" Hickory  
S75°E 39.55' Set Mag Nail & Remon Washer North face 10" Hickory  
West 127.47' South 1/4 corner of Section 36, T4N, R7E, Rose Township (L-13)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]  
Surveyor's Michigan License No. 17623

Date 6-1-99

