

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

345428

For corners in

Oakland  
(County)

Located in: Highland Township  
Corner Code #

1. Public Land Survey

T3N R7E L5

2. Property Controlling in Section

S T R SURVEY & RECONSTRUCTION

3. Miscellaneous Property in Sec.

S T R MAR 21 2000

LIBER 20560 PAGE 508  
\$7.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
09/20/1999 08:43:52 A.M. RECEIPT# 79775  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 8-31-99  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

**SECTION**

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
1823-GLO Wampler, D.S.; Set Post 5" Tamarack N26°E 17 Links; 5" Spruce S42°W 48 Links  
1.) 1989-Thompson, PS #23828; LCRC L.10771, Pg.200 - Fnd a 1/2" Pipe  
2.) 1977-Oakland County Road Commission Unrecorded Witnesses - Fnd a 3/4" Iron Pipe

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner as recovered is 9 feet West of the existing centerline of Duck Lake Road extending to the North & South, which has a bituminous surface. No lines of occupation to the East or West.

The corner was recovered based upon the found monumentation in the plats "SUPERVISOR'S PLAT NO. 5" & "VILLA NOVA".

**FIELD MEASUREMENTS BETWEEN**

**L-5 to K-5**  
GLO = 40.765 chains or 2690.49 Ft.  
No plat or sidwell distances  
2673.57 Ft. (GPS-MEA)

**L-5 to M-5**  
GLO = 40.765 chains or 2690.49 Ft. (M-5 in a lake)  
No plat or sidwell distances

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
L-5 I set a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623  
Monument Box  
N36°E 108.25' SW corner of house #3120  
S73°E 44.05' Set Mag Nail & Remon Washer North face Power Pole  
N87°W 11.95' Set Mag Nail & Remon Washer South face Power Pole  
S15°W 164.85' Set Mag Nail & Remon Washer East face Power Pole



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]  
Surveyor's Michigan License No. 17623

Date 9-6-99