

LAND-CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland
 (County)

Located in: Highland Township Corner Code #

1. Public Land Survey

T3N R7E L-9

T R

T R

T R

2. Property Controlling in Section

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

4. Lot No. _____ Recorded Plat _____

SECTION _____

5. Private Claims _____

38639
 LIBER 21077 PAGE 445
 \$7.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 02/08/2000 09:04:25 A.M. RECEIPT# 10181
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 1-12-2000 5/2
 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on October 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 20" White Oak N08°W 28 Links; 11" White Oak S32°E 56 Links;
 1.) 1976-Hooth PS #7966; LCRC L.6770, pgs 869 & 870 - Fnd a 1/2" Iron Rod
 2.) 1982-Bissell, PS #18655; LCRC L.8243, pg. 120 - Fnd a 1/2" Iron Rod and set a 1" Iron Pipe w/plastic cap
 3.) 1871-Surveyor unknown, object found not stated, no witnesses
 4.) 1983-Bissell, PS #18655; unrecorded Survey for M.D.N.R. - Fnd a 1/2" Iron Rod and set a 1" Iron Pipe w/plastic cap used same wit as 1982 LCRC
 5.) 1962-Oakland County Road Commission unrecorded witnesses - Fnd a 1/2" Rod

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner was recovered based upon a unrecorded Survey by Donald Bissell, PS #18655 dated February 9, 1983 by prorating the 1983 Survey with the 1999 measurements between L-9 and M-9 and holding the distance between L-10 and L-9 as shown on the 1983 Survey. I set a 5/8" x 24" iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a Monument Box located in a Concrete Gutter Pan on the East side of Duck Lake Road extending to the North & South, which has a bituminous surface, also in the existing centerline of Livingston Road extending to the West, which has a gravel surface.

FIELD MEASUREMENTS BETWEEN

L-9 to K-9

GLO = 40.75 chains or 2689.50 Ft.
 Unrecorded Survey by Donald Bissell, PS #18655 dated 2/9/83 for the M.D.N.R. (Sec 25) = 2680.40 Ft.
 2680.32 Ft. (GPS-MEA)

L-9 to M-9

GLO = 40.75 chains or 2689.50 Ft.
 Unrecorded Survey dated 1/20/1871 (Sec 25) = 40.21 Ft. & 2653.86 Ft.
 Unrecorded Survey by Donald Bissell, PS #18655 dated 2/9/83 for the M.D.N.R. (Sec 25) = 2696.52 Ft.
 2696.43 Ft. (GPS-MEA)

L-9 to L-10

No GLO
 Unrecorded Survey by Donald Bissell, PS #18655 dated 2/9/83 for M.D.N.R. (Sec 25) = 2626.83 Ft.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 L-9 I set a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 in a Monument Box
 N09°E 35.10' Set Mag Nail & Remon Washer NW face 12" Oak
 N37°W 78.10' Set Mag Nail & Remon Washer SW face 9" Cherry
 S66°W 147.90' Set Mag Nail & Remon Washer North face Power Pole
 S23°E 51.95' Set Mag Nail & Remon Washer SW face Power Pole



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
 Surveyor's Michigan License No. 17623

Date 1-13-00