

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

273058

For corners in

Oakland
(County)

Located In: Highland Township Corner Code #

LIBER 20329 PAGE 93
\$7.00 MISC RECORDING
\$2.00 REMONUMENTATION
07/29/1999 11:41:28 A.M. RECEIPT# 58913
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

1. Public Land Survey

T3N R7E M-1

2. Property Controlling in Section

S T R SECTION

3. Miscellaneous Property in Sec.

S T R MAR 21 2000

Compliance with ACT 345, P.A. 1990

APPROVED ON: 4-27-99 JJK
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat SECTION
5. Private Claims

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

I, Huston K. Kennedy, in a field survey on March 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1815-1816 GLO Holmes, D.S.; Post common to T3 & 4N, R7 & 8E, no witnesses
1.) 1979-King, PS #25852; LCRC L.7542, Pg.805 - Fnd a Railroad Spike
2.) 1997-Kovas, PS #33138; LCRC (for A-1 White Lake Twp.) L.17882, PG.454 - Fnd a 1/2" Re-rod w/yellow cap

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 5/8" iron Rod with a 2" diameter brass cap stamped Oakland County Remonumentation, PS #33138 located 2 feet East of the existing centerline of Eagle Road extending to the North & South, which has a gravel surface. A tree-fence row extends to the West. This corner is being accepted and used as a common corner with the Southeast corner of Section 36, T4N, R7E, Rose Township (M-13) and the Southwest corner of Section 31, T4N, R8E, Springfield Township (A-3) and the Northwest corner of Section 6, T3N, R8E, White Lake Township (A-1).

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 5/8" Iron Rod with a 2" diameter brass cap stamped Oakland County Remonumentation, PS #33138.

I accepted the found 5/8" Iron Rod with a 2" diameter brass cap stamped Oakland County Remonumentation, PS #33138 as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

M-1 to L-1
GLO = 40 chains or 2640.00 Ft.
No plat or sidwell distances
2533.83 Ft. (GPS-MEA)

M-1 to M-2
GLO = 40 chains or 2640.00 Ft.
No sidwell or plat distances
2779.61 Ft. (GPS-MEA)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-1 I accepted the found 5/8" iron Rod with a 2" diameter brass cap stamped Oakland County Remonumentation, PS #33138
S41°E 22.15' Fnd Mag Nail & Remon Washer stamped Oakland County Remon PS #33138 NE face 12" Hickory
N47°W 37.60' Fnd Mag Nail & Remon Washer stamped Oakland County Remon PS #33138 SW face 14" Oak
N18°E 32.40' Fnd Mag Nail & Remon Washer stamped Oakland County Remon PS #33138 NW face 10" Oak
S43°W 47.20' Fnd Mag Nail & Remon Washer stamped Oakland County Remon PS #33138 SE face 11" Cherry

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 4-30-99