

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

38640

Oakland  
 (County)

Located In: Highland Township Corner Code #

1. Public Land Survey

T3N R7E M-7  
 T R  
 T R  
 T R

2. Property Controlling in Section

S T R  
 S T R

3. Miscellaneous Property in Sec.

S T R  
 S T R

LIBER 21077 PAGE 446  
 \$9.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 02/08/2000 09:04:34 A.M. RECEIPT# 10181  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CABELL, CLERK/REGISTER OF DEEDS

Compare with  
 ACT 345, P.A. 1990

APPROVED ON: 12-7-99  
 OAKLAND COUNTY REMONUMENTATION  
 PUBLIC GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
  - 1817-GLO Wampler, D.S.; Set Post 18" White Oak S28°W 1.07 chains; 8" White Oak N56°E 35 links
  - 1.) 1976-Hooth, PS #7966; LCRC L.6770, pgs.871 & 872 - Fnd a 1" Pipe
  - 2.) 1997-Kovas, PS #33138; LCRC for (A-7 White Lake Twp.) L.17882, pg.457 - Fnd a 1/2" Iron Rod
  - 3.) Kostecke, PS #12584; unrecorded Survey - Fnd a 3/4" Pipe, no witnesses
  - 4.)
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
  - 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a Railroad Spike in the bituminous shoulder 21 feet North of the existing centerline of the West bound lane, also 7 feet North of the back of curb of M-59 Highway extending to the East & West, which has a bituminous surface, and a old fence line extending to the to the South.

I accepted the found Railroad Spike as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

M-7 to A-7

GLO =  
 Unrecorded Survey by Raymond J. Kostecke, PS #12584 dated 4/1/63 (Sec 13) = 336.68 Ft.  
 M.DOT Right of Way Map = 336.83 Ft.  
 336.17 Ft. (MEA 1999)

M-7 to M-6

No GLO, corner falls in White Lake  
 No sidwell or plat distances

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
  - M-7 I replaced the found Railroad Spike with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623 *IN A NEW MONUMENT BOX*
  - N02°E 85.20' Set Mag Nail & Remon Washer West face 28" Oak
  - N17°E 70.00' Set Mag Nail & Remon Washer NW face 24" Oak
  - N50°W 107.78' Set Mag Nail & Remon Washer SW face 13" Oak
  - S11°W 153.55' Set Mag Nail & Remon Washer West face Power Pole
  - N02°W 62.52' Fnd 1/2" capped Iron Rod

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]  
 Surveyor's Michigan License No. 17623

Date 12-10-99



LIBER 21077 # 447

**M-7 to M-8**

GLO = 40 chains or 2640.00 Ft.  
No sidwell or plat distances  
2669.07 Ft. (GPS-MEA)

**M-7 to L-7**

GLO = 40 chains or 2640.00 Ft.  
M.DOT Right of Way Map = 2698.11 Ft.  
2697.41 Ft. (GPS-MEA)

Angle @ L-7, M-7 - A-7  
Kostecek Survey = 90°09'00"  
M.DOT Right of Way Map = 90°08'40"  
90°13'39" (MEA 1999)

SURVEY &  
RECONSTRUCTION

MAR 21 2000

SECTION