

MAY 24 2000

LIBER 21146 042

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

59612

For corners in

<u>Oakland</u> (county)	Located in:	Corner Code #
	Waterford Township	
1. Public Land Survey	T3N R9E	A-3
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 21146 PAGE 42
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/29/2000 10:58:26 A.M. RECEIPT# 16518
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

ACT 345, P.A. 1999
APPROVED ON: 2-8-2000 JZ
OAKLAND COUNTY RE-MONUMENTATION
REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on April 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
There is one LCRC recorded at Oakland County; Scott 1973.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 4" diameter brass tablet, DNR Survey Marker, stamped Section 6 and 7 T.3N., R. 9E., 6/21/59, per the above referenced LCRC. This corner was validated with monumentation found in the Department of Conservation Survey of the Pontiac Lake Recreation Area. M-3 of White Lake Township should be 231.00' south of A-3 according to the Pontiac Lake Recreation Area Survey of 1959.

Recovered Witnesses:

- N 27°W 10.70' 20 penny nail in southwest side 24" Oak.
- N 13°E 11.78' nail with DNR washer in west side 22" Oak.
- S 82°W 26.44' nail with DNR washer.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Recovered State of Michigan Survey Marker for Sections 6 & 7, stamped T.3N., 9E.

- N 27°W 10.70' Mag nail with OCRT #24598 in west side of 24" Oak.
- N 13°E 11.78' Mag nail with OCRT #24598 in east side of 22" Oak.
- S 35°W 8.58' Mag nail with OCRT #24598 in northwest side 14" Oak.
- S 20°E 14.75' Mag nail with OCRT #24598 in northeast side 12" Sassafras.

Zp
R



Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 12/22/99