

MAY 24 2000

LIBER 21146 046

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

59614

For corners in

<u>Oakland</u> (county)	Located In: <u>Waterford Township</u>	Corner Code # <u>A-5</u>
1. Public Land Survey	T3N R9E	<u> </u>
	T <u> </u>	<u> </u>
	T <u> </u>	<u> </u>
	T <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u>	<u> </u>
	S <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u>	<u> </u>
	T <u> </u>	<u> </u>
	T <u> </u>	<u> </u>

LIBER 21146 PAGE 46
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 02/29/2000 10:58:27 A.M. RECEIPT# 16518
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS
 (City, State with
 ACT 74, P.A. 1970)

RECOVERED ON: 2-8-2000 JH
 OAKLAND COUNTY REMONUMENTATION
 1000 10000 10000 1000

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on April 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		18		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
 There is one LCRC recorded at Oakland County, D. Wayne Scott 1973.
 No witnesses of Mr. Scott's were recovered.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monumentation was found at this location. This corner was re-established per the Department of Conservation's Field Notes of 1947, D. Wayne Scott's Survey of August 1973 and the Department of Conservation's 1959 Pontiac Lake Recreation Area Survey. Mr. Kovas of Wade and Trim established M-5 of White Lake Township from the Conservation Field Notes of 1947 in which we agree with its location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

S 07°20'28"E 128.00' Set Mag nail with OCRT#24598 in east side utility pole.
 S 68°31'25"E 142.00' Set Mag nail with OCRT #24598 northeast side utility pole.
 N 17°04'53"E 151.46' Set Mag nail with OCRT #24598 west side 20" Oak.
 S 20°38'06"W 33.51' Set Mag nail with OCRT #24598 in south side 8" Pine.

Jp
n



Signed by Joseph C. Kapelczak
 Surveyor's Michigan License No. 24598

Date 12/22/99