

MAY 24 2000

LIBER 21146 : 050

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

59616

For corners in

<u>Oakland</u> (county)	Located In: <u>Waterford Township</u>	Corner Code # <u>A-11</u>
1. Public Land Survey	T3N R9E	<u>A-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

LIBER 21146 PAGE 50
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 02/29/2000 10:58:27 A.M. RECEIPT# 16518
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADELL, CLERK/REGISTER OF DEEDS

APPROVED ON: 11-2-99 JR
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on May 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.

There is one LCRC recorded at Oakland County; Redash, 1998.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered PK nail as set by John Redash of Giffels and Webster during the platting of Parkside Preserve of Waterford. This PK nail is 195.15' north of M-11 White Lake Township and on the township line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set monument box with 5/8" rerod and Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- N 24°58'W 71.85' Set Mag nail with OCRT #24598 in south side 24" Oak.
- N 12°44'E 103.95' Set Mag nail with OCRT #24598 in southeast side 18" Twin Oak.
- S 17°12'E 112.30' Set Mag nail with OCRT #24598 in northeast side 24" Oak
- S 64°13'W 39.39' Set Mag nail with OCRT #24598 in southeast face of utility pole.
- S 02°41'09"E 195.15' M-11 White Lake Township found Oakland County Remonumentation Brass Cap.

JP
n



Signed by Joseph C. Kapelczak

Date 12/22/99

Surveyor's Michigan License No. 24598