

SURVEY
REMONUMENTATION

MAY 24 2000

LIBER 21119 575

51674

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 21119 PAGE 575
\$9.00 MISC. RECORDING
\$2.00 REMONUMENTATION
02/18/2000 02:36:27 P.M. RECEIPT# 1420
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CABELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland (county)	Located In: Waterford Township	Corner Code # A-13
1. Public Land Survey	T3N R9E	A-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

12-7-99 J11
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on April 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
There is one LCRC recorded in Oakland County by Kennedy in 1999 for the West Bloomfield/White Lake Township corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered 5/8" rerod with Oakland County Remonumentation Brass Cap stamped #17623 in monument box. It should be noted that we also recovered a 1/2" iron 5.05' east of this monument box which represents A-13 of Waterford Township. The above referenced monument box is the extension of the southerly Waterford Township line as its intersection with the White Lake Township line as M-13 of White Lake Township is 182.42' south of A-13 Waterford Township. The 1/2" iron was validated with monumentation found in the Valley Forge Subdivision.

Recovered Witnesses:

- S 29°W 55.88' Found PK with washer #21566 northwest side power pole.
- S 29°W 55.99' Found PK with washer #12578 southeast side power pole.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Recovered 5/8" rerod with Oakland County Remonumentation Brass Cap stamped #17623 in monument box.

Set Witnesses:

- S 20°E 118.02' set Mag nail with OCRT #24598 in east side power pole.
- S 29°W 55.88' set Mag nail with OCRT #24598 northwest side power pole.
- N 60°W 69.69' set Mag nail with washer stamped #24598 northside 4" Maple.
- N 61°E 120.13' set Mag nail with OCRT #24598 south side light pole.



Signed by Joseph C. Kapelczak Date 12/15/99
Surveyor's Michigan License No. 24598