

MAY 24 2000

LIBER 21146 052

SECTION

LAND CORNER RECORDATION CERTIFICATE 59617  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Waterford Township	
1. Public Land Survey	T3N R9E	B-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 21146 PAGE 52  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
02/29/2000 10:58:27 A.M. RECEIPT# 16518  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CABELL, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 135, P.A. 1990

APPROVED ON: 11-3-99 512  
CLERK COUNTY REMONUMENTATION  
TASK FORCE COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on May 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		5	5	4	3	2							
3													
4	7	8	9	10	11	12							
5													
6	18	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.

There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monumentation was recovered at this location. B-13 of Independence Township was recovered as set by Mr. Tim Hart. This corner was re-established from an unrecorded survey of All Saints Cemetery prepared for Mt. Olivet Cemetery by George DeLay; a copy of which has not been obtained as of this date from Mr. DeLay. Validated the location of this corner with a calculated distance plus a Sidwell distance along the north line of Section 6. B-1 as set from the above described method is 0.07' north of the township line and 63.34' east of B-13 Independence Township.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- N 86°24'10"E 116.63' Set Mag nail with OCRT #24598 south side 22" Oak.
- S 86°20'33"E 126.36' Set Mag nail with OCRT #24598 northwest side 12" Oak.
- N 79°11'06"E 161.24' Set Mag nail with OCRT #24598 west side 16" Elm.
- S 78°57'24"E 174.97' Set Mag nail with OCRT #24598 west side 10" Maple.
- S 87°24'39"W 63.34' found concrete monument B-13 Independence Township.



Signed by Joseph C. Kapelczak  
Surveyor's Michigan License No. 24598

Date 12/22/99