

MAY 24 2000

LIBER 21119 577

SECTION

51675

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 21119 PAGE 577
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/18/2000 02:36:27 P.M. RECEIPT# 14203
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

<u>Oakland</u> (county)	Located In:	Corner Code #
	Waterford Township	
1. Public Land Survey	T3N R9E	B-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with ACT 345, P.A. 1990
APPROVED ON: 12-7-99 JH
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on May 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3	7	8	9	10	11	12						
4	13	14	15	16	17	18						
5	19	20	21	22	23	24						
6	25	26	27	28	29	30						
7	31	32	33	34	35	36						
8												
9												
10												
11												
12												
13												

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a concrete monument set by Thomas Smith at this location. Validated location with monumentation found in Maceday Knolls Subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap stamped #24598 on top of existing concrete monument.

- N 48°W 58.99' Mag nail with OCRT #24598 northeast face 6" Poplar.
- N 10°E 52.24' Mag nail with OCRT #24598 8" Poplar.
- N 38°E 64.42' Mag nail with OCRT #24598 southeast face 12" Poplar.
- S 66°E 93.22' Mag nail with OCRT #24598 south face 14" Poplar.

JKR



Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 12/2/99