

SURVEY & REMONUMENTATION

LIBER 15288 PG 550

MAR 10 95 040460

OK - T. SMITH

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OAKLAND

COMMISSION

Located In: WATERFORD Corner Code #

7.00 MISC RECORDING CHG - IN HOUSE
2.00 REMON CHG - IN HOUSE
10 MAR 95 4:12 P.M. RECEIPT# 1788
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-30-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3 N R 9 E B-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

I, THOMAS M. SMITH, in a field survey on DECEMBER 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A dot is marked at row 5, column C.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST, G.L.O. ROAD COMMISSION 1/2 INCH ROD
1817 1/2 ROD, 1963 L.C.R.C., L.6165, PG. 137 1973

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A 1/2" ROD IN A MONUMENT BOX AT THE INTERESTION OF GALE ROAD & WILLIAMS LAKE ROAD EXTENDED WEST & NORTH. CORNER POSITION WAS VERIFIED FROM ROAD COMMISSION WITNESSES AND THE LAND CORNER CERTIFICATE RECORDED IN LIBER 6165, PAGE 137.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5, I REPLACED THE 1/2" ROD WITH A 5/8" ROD WITH BRASS CAP #31606 IN THE MONUMENT BOX.
N 10 E, 64.12 to remon tag W. Side 12" Pine
S 35 W, 91.70 to remon tag E. side 10" catalpa
N 50 E, 108.25 to remon tag W. side Chinese Elm
S 75 W, 103.24 to remon tag S.E. side 7" Cedar

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYOR AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]
Surveyor's Michigan License No. 31606

Date DECEMBER 19, 1994