

**SURVEY & REMONUMENTATION**

MAY 24 2000

LIBER 21119 585

51679

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 21119 PAGE 585  
 \$9.00 MISC RECORDING  
 \$2.00 REMONUMENTATION  
 02/18/2000 02:36:27 P.M. RECEIPT# 141  
 PAID RECORDED - OAKLAND COUNTY  
 G. WILLIAM CADDELL, CLERK/REGISTER OF

For corners in

Oakland (county)	Located In: Waterford Township	Corner Code #
1. Public Land Survey	T3N R9E	C-7
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling In Section	S___ T___	_____
	S___ T___	_____
3. Miscellaneous Property in Sec.	S___ T___	_____
	S___ T___	_____

Compliance with  
 ACT 345, P.A. 1990  
 APPROVED ON: 11-24-99 JTL  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapeiczak, in a field survey on May 20, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2		5		5		4		3		2		1
3												
4	7		8		9		10		11			
5												
6	18		17		16		15		14			
7												
8	19		20		21		22		23			
9												
10	30		28		26		27		26			
11												
12	31		32		33		34		35			
13												

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
 There is one LCRC recorded at Oakland County; Smith 1995.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron rod in monument box in the middle of the east bound (north lane) of M-59 Highway and the centerline of Hospital Road running south. The corner lies approximately 13' south of the center turn lane of M-59 highway. Validated the location of this corner with monumentation found in S/P 31.

Recovered Witnesses:

- N 29°W 73.69' PK nail east face utility light pole.
- N 45°E 72.46' Mag nail west face light pole.
- S 37°W 49.39' Mag nail east face utility pole.
- S 66°E 129.14' PK nail west face utility pole.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Oakland County Remonumentation Brass Cap stamped #24598 in existing monument box.

Set Witnesses:

- N 29°W 73.69' Mag nail with OCRT #24598 in east face utility pole.
- N 45°E 72.54' Mag nail with OCRT #24598 in west face light pole.
- S 37°W 49.39' Mag nail with OCRT #24598 in east face utility pole.
- S 66°E 129.14' PK nail west face utility pole.



Signed by Joseph C. Kapeiczak

Date 11/23/99

Surveyor's Michigan License No. 24598