

**SURVEY &
REMONUMENTATION**

LIBER 15290 PG 575

MAR 14 95 04T389
OK - T. SMITH

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE \$ 7.00 MISC RECORDING CHG - IN HOUSE
\$ 2.00 REMON CHG - IN HOUSE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
OAKLAND
(County)

COMMISSION

Located in: **WATERFORD**

Corner Code #

14 MAR 95 9:14 A.M. RECEIPT# 45B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>3</u> N R <u>9</u> E | <u>C-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-30-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, THOMAS M. SMITH, in a field survey on DECEMBER 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST G.L.O. 1817	1/2" IRON ROD L.C.R.C. L. 12208 P. 633 J. SMITH, 1991	1/2" IRON ROD UNRECORDED SURVEY G. BOSS, 1993	STONE/IRON PIN M. BALDWIN, 1926
---------------------	--	---	------------------------------------

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A 1/2" ROD IN A MONUMENT BOX IN THE CENTERLINE OF HOSPITAL ROAD. I RECOVERED THE CORNER BY USING THE WITNESSES FROM A SURVEY BY G. BOSS(1993) ALSO FROM ADJACENT CONCRETE MONUMENT TO THE EAST AND NORTHWESTERLY 165'+/-. HOSPITAL ROAD WAS RECENTLY PAVED AND THE BOX WAS INSTALLED AT THAT TIME.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10: I REPLACED THE 1/2" ROD WITH A 5/8" ROD WITH A BRASS CAP #31606 IN THE MONUMENT BOX.
S 50 W. 83.74' to remon tag N. side quad elm.
N 70 W. 32.31' to remon tag S. side 14" elm.
N 45 E. 67.70' to remon tag 2.5' high S. side 5" spruce.
S 80 E. 60.66' to concrete monument.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by [Signature] Date DECEMBER 19, 1994
Surveyor's Michigan License No. 31606