

SURVEY &  
REMONUMENTATION

MAY 24 2000

LIBER 21119 PAGE 587

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

51680

For corners in

Oakland (county)	Located In:	Corner Code #
1. Public Land Survey	Rose Township Waren POND T3N R9E	C-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 21119 PAGE 587  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
02/18/2000 02:36:27 P.M. RECEIPT# 14203  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

APPROVED FOR  
12 15 99 JZ  
REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on April 13, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	0	1	2	3	4	5	6	7	8	9	10	11
3	12	13	14	15	16	17	18	19	20	21	22	23
4	24	25	26	27	28	29	30	31	32	33	34	35
5	36	37	38	39	40	41	42	43	44	45	46	47
6	48	49	50	51	52	53	54	55	56	57	58	59
7	60	61	62	63	64	65	66	67	68	69	70	71
8	72	73	74	75	76	77	78	79	80	81	82	83
9	84	85	86	87	88	89	90	91	92	93	94	95
10	96	97	98	99	100	101	102	103	104	105	106	107
11	108	109	110	111	112	113	114	115	116	117	118	119
12	120	121	122	123	124	125	126	127	128	129	130	131
13	132	133	134	135	136	137	138	139	140	141	142	143

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered monument box in centerline Hospital Road and centerline Cooley Lake Road. This corner was validated with monumentation found in Keith Acres Subdivision and S/P #55. C-1 of West Bloomfield Township is 25.37' east of this corner and on the township line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rerod with Oakland County Remonumentation Brass Cap #24598 in existing monument box in centerline Hospital Road and Cooley Lake Road.

Set Witnesses:

- S 33°E 39.39' set Mag nail with OCRT #24598 southwest side power pole.
- S 80°E 96.36' set Mag nail with OCRT #24598 north side power pole.
- N 71°E 120.38' set Mag nail with OCRT #24598 north side power pole.
- N 30°W 53.77' set Mag nail with OCRT #24598 northeast side MBT pole.

*JZ*



Signed by Joseph C. Kapelczak

Date 12/22/99

Surveyor's Michigan License No. 24598