

MAY 24 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

59620

For corners in

Table with columns: Oakland (county), Located In: Waterford Township, Corner Code # D-1. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

LIBER 21146 PAGE 58
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/29/2000 10:58:27 A.M. RECEIPT# 16518
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

Compliance with ACT 74, P.A. 1970

APPROVED ON 12-14-99 JL
OAKLAND COUNTY REMONUMENTATION
PEER GROUP DISMISSED

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on June 1, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. Cell D-1 is marked with a dot.

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monumentation was recovered at this location. This corner was re-established by setting D-1 midway between C-1 and E-1 on the Independence Township line. D-1 is 42.05' west of D-13 Independence Township.

Recovered Witnesses:

- N 10°W 47.22' PK nail with OCRT #19843 east face 8" Cherry.
S 40°W 22.25' PK nail with OCRT #19843 east face 14" Pine.
S 85°E 71.99' PK nail with OCRT #19843 north face power pole.
West 96.74' PK nail with OCRT #19843 north face power pole.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete nonument with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- S 76°11'39"W 38.80' Set Mag nail with OCRT #24598 south side 8" Cherry.
S 37°01'54"E 63.32' Set Mag nial with OCRT #24598 east side 18" Pine.
S 64°52'09"W 43.80' found PK nail with OCRT #19843 north side of utility pole.
S 59°15'11"E 138.26' found PK nail with OCRT #19843 north face utility pole.
N 87°21'29"E 42.05' found concrete monument D-13 Independence Township.

Handwritten initials 'hp' and 'R'.



Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 12/22/99