

SURVEY & REMONUMENTATION

LIBER **15288** PC **541**

MAR 10 95 04 04 51
OK - T. SMITH

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE 7.00 MISC RECORDING CHG - IN HOUSE
Filing Requirement of Act 74, Mich. P.A. 1970; 2.00 REMON CHG - IN HOUSE

For corners in

COMMISSION

OAKLAND
(County)

Located In: WATERFORD Corner Code ##

10 MAR 95 4:10 P.M. RECEIPT# 1788
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-30-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

1. Public Land Survey T 3 N R 9 E E-1
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, THOMAS M. SMITH, in a field survey on DECEMBER 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST,	CONCRETE MON.
G.L.O. 1817	ELMER F. BARNES PLAT 1926.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A CONCRETE MONUMENT AS REPRESENTED ON THE PLAT OF ELMER F. BARNES.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1: FOUND A CONCRETE MONUMENT. I PLACED THE OAKLAND CO. BRASS TAG ON EXISTING MONUMENT
S 10 W. 40.10' to remon tag E. side 10" oak
S 20 E. 24.25' to remon tag E. side 7" oak
S 80 E. 11.59' to remon tag N. side 14' oak
EAST 84.80' to remon tag N. side 16" oak

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by [Signature]

Date DECEMBER 19, 1994

Surveyor's Michigan License No. 31606