

MAY 24 2000

LIBER 21119 601

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1979

51687

LIBER 21119 PAGE 601  
\$9.00 MISE RECORDING  
\$2.00 REMONUMENTATION  
02/18/2000 02:36:27 P.M. RECEIPT# 14203  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland (county)	Located in: Reese Township WATERFORD	Corner Code # E-13
1. Public Land Survey	T3N R9E	E-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on March 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There are two LCRC's recorded at Oakland County; Patterson 1990 and Kapelczak 1991.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered concrete monument with Oakland County Remonumentation Brass Cap stamped #31606 at this location. This corner lies 21.46' west of E-1 West Bloomfield Township and was validated with monumentation found in Pilgrim Hills Subdivision #2.

Recovered Witnesses:

S 25°E 34.17' PK nail east side 12" Cherry.  
S 85°E 25.24' PK nail south side base 24"/10" Oak.  
South 35.83' PK nail with OCRT # 31606 in west side 16" Oak.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Recovered concrete monument with Oakland County Remonumentation Brass Cap stamped #31606.

Set Witnesses:

North 2.94' set Mag nail with OCRT #24598 west side Twin 34" Oak.  
S 25°E 34.17' set Mag nail with OCRT #24598 east side 12" Cherry.  
S 85°E 25.24' Mag nail with OCRT #24598 south side Twin 24"/10" Oak.  
South 35.83' PK nail with OCRT #24598 #31606 west side 16" Oak.  
N 87°22'19"E 21.46' found concrete monument E-1 West Bloomfield Township



Signed by Joseph C. Kapelczak Date 12/22/99  
Surveyor's Michigan License No. 24598

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	13		17		16		15		14		13	
7												
8	18		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

2p  
R