

MAY 24 2000

LIBER 21119 607

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

51690

LIBER 21119 PAGE 607
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/18/2000 02:36:27 P.M. RECEIPT# 142
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF

For corners in

Oakland (county)	Located In: Rose Township WATERFORD	Corner Code #
1. Public Land Survey	T3N R9E	G-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-14-99 JIL
OAKLAND COUNTY REMONUMENTATION
PER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims

I, Joseph C. Kapelczak, in a field survey on March 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		18		19		20		21	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
There is one LCRC recorded at Oakland County; Williams 1979.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No witnesses were recovered at this location.

No monumentation was recovered at this location as the area is filled with broken concrete spoils. Reestablished and validated this corner with monumentation found in Drayton Heights No. 1 Subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- S 76°31'W 234.18' set Mag nail north side 24" Willow.
- S 33°03'W 149.52' set Mag nail east side 8" Pine.
- S 31°08'E 66.02' set Mag nail west side Tw'n 12" Box Elder
- S 8°34'W 125.74' set Mag nail east side 10" Maple.
- N 55°24'W 4.56' set Mag nail south side of SE bench post.

2P
R



Signed by Joseph C. Kapelczak

Date 12/13/99

Surveyor's Michigan License No. 24598