

SURVEY &
REMONUMENTATION

LIBER. 15292 PG. 376

MAR 15 95 04 1988

OK - T. SMITH

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
OAKLAND

COMMISSION

Located In: WATERFORD Corner Code #

- | | | | | | | | |
|------------------------------------|---|---|---|---|---|----|-----|
| 1. Public Land Survey | T | 3 | N | R | 9 | E. | G-7 |
| | T | | R | | | | |
| | T | | R | | | | |
| | T | | R | | | | |
| 2. Property Controlling in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous Property in Sec. | S | | T | | R | | |
| | S | | T | | R | | |

7.00 NISC RECORDING CHG - IN HOUSE
\$ 2.00 REMON CHG - IN HOUSE
15 MAR 95 8:09 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-30-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, THOMAS M. SMITH, in a field survey on NOVEMBER 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST, G.L.O. 1817 IRON PIPE ROAD COMMISSION 1963

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A 1/2" ROD IN A MONUMENT BOX. THIS CORNER FIT WELL WITH THE PLAT OF WATKINS-LAKELANDS NO. 1. THE ROAD COMMISSION DATES THE MONUMENT BACK TO 1963.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7: I REPLACED IRON WITH A 5/8" ROD WITH BRASS CAP #31606
N 80 E. 80.36' to N.W. corner brick wall extention of building.
N 40 W. 88.44' to remon tag S.W. side 4" maple.
N 75 W. 73.65' to bend point brick fence.
N 10 E. 131.94' to concrete monument.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE AVILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by [Signature] Date DECEMBER 19, 1994
Surveyor's Michigan License No. 31606

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	10	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

THOMAS M. SMITH LAND SURVEYOR NO. 31606