

MAY 24 2000

SECTION

LIBER 21119 609

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

51691

For corners in

Oakland (county)	Located In:	Corner Code #
	Ross Township WATERFORD	
1. Public Land Survey	T3N R9E	G-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 21119 PAGE 609
 \$9.00 MISC RECORDING
 \$2.00 REMONUMENTATION
 02/18/2000 02:36:27 P.M. RECEIPT# 1
 PAID RECORDED - OAKLAND COUNTY
 G. WILLIAM CADDELL, CLERK/REGISTER D

RECEIVED
 12-14-99 512
 OAKLAND COUNTY REMONUMENTATION
 GROUP OF COURTESY

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, **Joseph C. Kapelczak**, in a field survey on **April 28, 1999**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	8		5		4		3		2			
3												
4	7		6		9		10		11			
5												
6	16		17		18		19		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
 There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner was re-established using monumentation found on the rear line of Lots 8 and 9 of Crescent Woods Lake Subdivision and validated with monumentation found on the south line of S/P #5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

S 72°00'28"W 24.11' Mag nail with OCRT #24598 southeast side 8" Maple (part of quad Maple).
 S 55°26'W 16.31' set Mag nail with OCRT #24598 east side 14" Poplar.
 S 47°13'E 12.51' set Mag nail with OCRT #24598 southwest side 18" Poplar
 N 11°57'W 79.31' set Mag nail with OCRT #24598 east side 14" Poplar.

MP
R



Signed by Joseph C. Kapelczak
 Surveyor's Michigan License No. 24598

Date 12/22/99