

MAY 24 2000

LIBER 21146 068

SECTION

59625

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 21146 PAGE 68
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/29/2000 10:58:27 A.M. RECEIPT# 16518
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

Oakland (county)	Located In: Rose Township WATER FORK	Corner Code #
1. Public Land Survey	T3N R9E	H-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 1-12-2000
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on May 26, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	13		17		18		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monumentation was found at this location. This corner was re-established using G-9 and irons found in an R.J. McCoy Survey 2/1/99, along with a distance proportioned between G-9 and I-9 using the plat of Stringham Farms Subdivision and Crescent Lake Highlands Subdivision and distances from recorded deeds.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- S 49°56'28"W 31.33' Mag nail with OCRT #24598 south side 24" Oak.
- S 04°19'E 34.52' Mag nail with OCRT #24598 west face 10" Oak.
- S 48°00'36"E 29.59' Mag nail with OCRT #24598 south face 20" Maple.
- N 34°30'E 9.73' Mag nail with OCRT #24598 east face 14" Maple.

2p
R



Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 12/22/99