

MAY 24 2000

LIBER 21146 070

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

59626

LIBER 21146 PAGE 70  
\$9.00 MISC RECORDING  
\$2.00 REMONUMENTATION  
02/29/2000 10:58:27 A.M. RECEIPT# 16518  
PAID RECORDED - OAKLAND COUNTY  
G. WILLIAM CABELL, CLERK/REGISTER OF DEEDS

For corners in

<u>Oakland</u> (county)	Located in:	Corner Code #
	Waterford Township	
1. Public Land Survey	T3N R9E	H-13
	T_____ R_____	_____
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling In Section	S_____ T_____	R_____
	S_____ T_____	R_____
3. Miscellaneous Property in Sec.	S_____ T_____	R_____
	S_____ T_____	R_____

Compliance with  
ACT 343, P.A. 1990  
PROVED ON: 11-3-99 JK  
OAKLAND COUNTY REMONUMENTATION  
FORUM GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Joseph C. Kapelczak, in a field survey on 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.  
There are no LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered a 1/2" iron at this location 10'± north of Bumper Block Drive, Dodge Park #4. This iron is located 38.01' west of H-1 West Bloomfield Township and on the West Bloomfield Township Line. Validated this location with lot corners recovered in Forest Bay Condo's, Meniwater's and Elizabeth Cass Heights Subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set concrete monument with Oakland County Remonumentation Brass Cap stamped #24598.

Set Witnesses:

- S 67°W 30.33' PK nail with OCRT #17623 north face 6" Locust.
- N 4°E 140.19' Mag nail with OCRT # 24598 east face 12" Oak.
- S 74°E 98.59' Mag nail with OCRT #24598 south face 8" Oak.
- N 81°W 91.67' Mag nail with OCRT #24598 south face 10" Poplar.

JK  
R



Signed by Joseph C. Kapelczak Date 12/22/99

Surveyor's Michigan License No. 24598