

**SURVEY & REMONUMENTATION**

LIBER 15292 PG 375

MAR 15 95 04 1987

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

OK - T. SMITH

For corners in  
OAKLAND  
(County)

**COMMISSION**

Located in: WATERFORD Corner Code #

7.00 MISC RECORDING CHG - IN HOUSE  
\$ 2.00 REMON CHG - IN HOUSE  
15 MAR 95 8:09 A.M. RECEIPT# 88  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-30-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>3</u> N R <u>9</u> E | <u>I-2</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, THOMAS M. SMITH, in a field survey on NOVEMBER 26, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

POST, G.L.O. 1817	1" IRON PIPE L.C.R.C. L.13634 P. 644 SCHARL, 1993	CONCRETE MON. LAKE OAKLAND SUB. 1941.
----------------------	--	---

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I FOUND A 1" IRON PIPE AT THE REAR OF LOT 1, KRIVETSKY'S LAKE OAKLAND SUBDIVISION, IRON PIPE FITS CLOSELY WITH THE ABUTTING PLATTED LOTS OF ALL ADJACENT PLATS.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-2: I RREPLACED THE PIPE WITH A CONCRETE MONUMENT WITH A BRASS CAP #31606  
S 75 E. 30.70' to remon tag N. side 16" oak.  
EAST 1.82' to remon tag S. side 28" oak.  
SOUTH 31.59' to remon tag E. side 14" oak.  
S 75 W. 65.76' to remon tag S. side 20" oak.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS ACCEPTED BY PROFESSIONAL SURVEYORS AS THE AVILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by 

Date DECEMBER 19, 1994

Surveyor's Michigan License No. 31606

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

*Handwritten initials/signature*

