

MAY 24 2000

LIBER 21119 613

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

51693

LIBER 21119 PAGE 613
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/18/2000 02:36:27 P.M. RECEIPT# 14202
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER OF DEEDS

For corners in

<u>Oakland</u> (county)	Located In: <u>Rose Township</u> <u>Waterford</u>	Corner Code # <u>1-3</u>
1. Public Land Survey	T <u>3N</u> R <u>9E</u>	<u>1-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____	_____
	S _____ T _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____	_____
	S _____ T _____	_____

APPROVED ON: 12-14-99 JKL
OAKLAND COUNTY REMONUMENTATION
NEED GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on March 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
There is one LCRC recorded at Oakland County; Scharl 1993.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monumentation was recovered at this location. Re-established this corner from monumentation located on the east and south line of S/P #10. Validated the location of this corner with monumentation found on the east line of Loon Lake Heights Subdivision.

Recovered Witnesses:

S 76°E 114.06' double headed nail with OCRC washer east face Detroit Edison MBT pole.
S 03°E 25.13' PK nail north face Detroit Edison MBT pole.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" iron with OCRT stamped #24598 in new monument box.

Set Witnesses:

S 75°49'W 113.78' Set Magnail with washer north side of power pole.
S 03°40'E 25.54' Set Mag nail with washer east side of power pole.
S 76°24'E 82.21' set Mag nail with washer northeast side of power pole.
S 28° 13'E 56.47' set Mag nail with remonumentation washer east side 16" Oak.

JKL
h



Signed by Joseph C. Kapelczak Date 12/22/99

Surveyor's/Michigan License No. 24598