

MAY 24 2000

SECTION

LIBER 21119 615

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

51694

For corners in

LIBER 21119 PAGE 615
\$9.00 MISC RECORDING
\$2.00 REMONUMENTATION
02/18/2000 02:36:27 P.M. RECEIPT # 1
PAID RECORDED - OAKLAND COUNTY
G. WILLIAM CADDELL, CLERK/REGISTER

| Oakland (county) | Located In: Waterford Township | Corner Code # |
|---------------------------------------|-----------------------------------|---------------|
| 1. Public Land Survey | T3N R9E | I-4 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Compliance with
ACT 345, P.A. 1999
PROVED ON: 12-7-99 JH
OAKLAND COUNTY REMONUMENTATION
RECORDING DIVISION

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

I, Joseph C. Kapelczak, in a field survey on March 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K |
|----|---|---|---|---|---|---|---|---|---|---|---|
| 2 | | | | | | | | | | | |
| 3 | | | | | | | | | | | |
| 4 | | | | | | | | | | | |
| 5 | | | | | | | | | | | |
| 6 | | | | | | | | | | | |
| 7 | | | | | | | | | | | |
| 8 | | | | | | | | | | | |
| 9 | | | | | | | | | | | |
| 10 | | | | | | | | | | | |
| 11 | | | | | | | | | | | |
| 12 | | | | | | | | | | | |
| 13 | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

Set post in 1816 G.L.O. Survey.
There are LCRC's recorded at Oakland County.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The location of this corner lies within a canal inlet of Loon Lake. This corner was re-established with monumentation found in Loon Lake Woods No. 1 and Loon Lake Woods No. 2 along with the tax descriptions for parcel 13-11-102-029. A reference monument was placed on the west line of Loon Lake Woods No. 2, 500.00' north of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Reference Monument with Oakland County Remonumentation Brass Cap #24598.

Set Witnesses:

- S 70°E (5.72') set Mag nail with OCRT #24598 in north side 24" Maple.
- N 25°W (13.90') set Mag nail with OCRT #24598 in east side of 8" Oak.
- West (17.31') set Mag nail with OCRT #24598 in north side 8" Cherry.
- N 19°E (32.74') set Mag nail with OCRT #24598 in west side of 8" Maple in a group of 4 Maples.

MI SPC NAD 83 (1986) MI South Zone (Int'l Ft.)

| | | |
|-----------|-------------|---------------|
| I-4 | N432573.939 | E13391993.842 |
| I-3 | N435269.611 | E13391871.155 |
| REF. MON. | N433073.414 | E13391970.956 |

2p
R



Signed by Joseph C. Kapelczak
Surveyor's Michigan License No. 24598

Date 12/22/99