

SURVEY & REMONUMENTATION

LIBER 15292 PG. 373

MAR 15 95 04 1985

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

For corners in OAKLAND (County)

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

Located in: WATERFORD Corner Code #

\$ 7.00 MISC RECORDING CHG - IN HOUSE
\$ 2.00 REMON CHG - IN HOUSE
15 MAR 95 8:09 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-30-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3 N R 9 E I-10
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

I, THOMAS M. SMITH, in a field survey on NOVEMBER 26, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST, G.L.O. 1817 " X " IN PAVEMENT ROAD COMMISSION 1963

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A NAIL IN A MONUMENT BOX. THE CORNER FIT WELL WITH THE PLAT OF STRINGHAM FARMS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10: I REPLACED NAIL WITH A 5/8" ROD WITH BRASS CAP #31606.
N 20 E. 66.16' to N.E. corner planter box to the front of building.
N 20 W. 75.11' to remon tag S.W. side 10"pine.
S 35 W. 85.93' to remon tag E. side 18" maple.
S 05 W. 103.39' to remon tag E. side 18" maple.

the selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the original corner.

Signed by [Signature]

Date DECEMBER 19, 1994

Surveyor's Michigan License No. 31606

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column G and row 10.

Handwritten initials/signature

