SURVEY & REMONUMENTATION

LIBER 15292 PG 368

MAR 15 95 04 1980

MAY - 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in OAKLAND (County) Located In: WATERFORD Corner Code #

$ 7.00 MISC RECORDING CHG - IN HOUSE
$ 2.00 REMON CHG - IN HOUSE
15 MAR 95 8:08 A.M. RECEIPT# 8B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-30-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

1. Public Land Survey T 3 N R 9 E I-12
   T ___ R ___
   T ___ R ___
   T ___ R ___
2. Property Controlling S ___ T ___ R ___
   in Section S ___ T ___ R ___
3. Miscellaneous S ___ T ___ R ___
   Property in Sec. S ___ T ___ R ___
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



I, THOMAS M. SMITH, in a field survey on NOVEMBER 26, 19 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST, G.L.O. 1817
BRASS DISC IN MON.
L.C.R.C.
L. 7326 P. 726
LOHFF, 1978

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A BRASS DISK IN THE ASPHALT OF CASS ELIZABETH LAKE ROAD & PARKWAY. I VERIFIED THE CORNER FROM THE L.C.R.C. BY LOHFF. I MEASURED SOUTH TO I-13 AND CLOSELY FIT THE MENIWATER SUBDIVISION DIMENSION.

STATE OF MICHIGAN
THOMAS M. SMITH LAND SURVEYOR NO. 31606
LICENSED LAND SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12: I LEFT THE BRASS DISK ON TOP OF A PIPE IN A NEW MONUMENT BOX.
S 45 E. 42.92' to most easterly corner C.B. frame.
S 45 W. 114.75' to remon tag S. side 6" box elder.
N 10 W. 30.60' to remon tag E. side wood sign post.
N 10 E. 105.90' to top center of south bolt in conc. base.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SERVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by _____ Date DECEMBER 19, 1994

Surveyor's Michigan License No. 31606

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983