

SURVEY &
REMONUMENTATION

LIBER 15292 PG 367

MAR 15 95 04T979

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

For corners in

OAKLAND

(County)

COMMISSION

Located In: WATERFORD

Corner Code #

- | | | | | | | | |
|------------------------------------|---|---|---|---|---|---|------|
| 1. Public Land Survey | T | 3 | N | R | 9 | E | I-13 |
| | T | | R | | | | |
| | T | | R | | | | |
| | T | | R | | | | |
| 2. Property Controlling in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous Property in Sec. | S | | T | | R | | |
| | S | | T | | R | | |

\$ 7.00 MISC RECORDING CHG - IN HOUSE
\$ 2.00 REMON CHG - IN HOUSE
13 MAR 95 8:08 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-30-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, THOMAS M. SMITH, in a field survey on NOVEMBER 26, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

POST, G.L.O. 1817	IRON PIPE ROAD COMMISSION 1963	3/4" IRON PIPE L.C.R.C. L. 11501 P. 267 LOHFF, 1990
----------------------	--------------------------------------	--

Handwritten signature/initials

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I FOUND A 3/4 PIPE IN THE ASPHALT (NORTHBOUND LANE) OF PARKWAY DRIVE DIMENSIONS MEASURED NORTH CLOSELY FIT MENIWATERS SUBDIVISION PLAT DISTANCE. I VERIFIED CORNER FROM LOHFF WITNESS AND THE ROAD COMMISSION WITNESS (WEST TO HICKORY).



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13: I REPLACED THE 3/4" IRON PIPE WITH A 5/8" ROD WITH BRASS CAP # 31606
S 85 W. 33.78' to remon tag S. side 28" hickory
N 45 E. 90.10' to S.W. foundation corner HSE. #1571
S 85 E. 68.65' to S.W. foundation corner HSE. #1575
S 40 W. 111.13' to most easterly foundation corner HSE. #4028

THE SELECTED LOCATION IS ACCEPTED BY ME AND GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by *Thomas M. Smith*
31606

Date DECEMBER 19, 1994

Surveyor's Michigan License No. _____